

A Message from the President



Editorial by
Patrick Malone
ASBI President
PMalone@pcl.com


In the Fall of 2018, we elected to move forward with planning for our 2020 convention setting the stage in Austin, Texas. The theme was regarding ASBI's vision of the future and the convention name was ASBI 2020 Vision. The idea was to bring forward some of the brightest people in the industry to "think tank" the future of transportation and how it was being molded by modern technology and cultural shifts. We thought of how electric vehicles would move the daily commuter and freight in the USA and how this would change design conditions. We discussed how flying vehicles could alter the overall architecture of our highway system and even buildings themselves. The gist of the conversation was that the transportation industry is based on a timescale which operates at a completely different rate than that of today's society. It has been stated that for a transportation project to come to fruition in the United States, it takes nearly 15 years from conception to completion, a rate that fails in comparison to the expectations of today's society.

We have, in only a few months, found ourselves with a complete paradigm shift beyond what we were planning in that board room. Once crowded highway commutes, that were an hour or longer, are now completed in a quarter of the time due to being almost barren. Commuters found that they could work from home when required to do so, and it is a matter of time as to whether that becomes the new norm. Freight that was once able to be compartmentalized through shipping direct to the large box stores changed as well. People who were not comfortable with ordering online, have significantly increased their use of this platform, potentially accelerating the shift from brick and mortar stores to residential delivery. In the building industry, business owners are already re-thinking how they operate and what size facilities they need to meet the potentially new ways of doing business.

What the future will hold is still just speculation, one that will unravel in the coming months and years, but without a doubt the events over these past few months will leave an indelible mark on our industry. As post-war conditions drove the innovation to develop segmental bridges, it will create new changes and new expectations within the public that will drive the metronome that we must keep pace with. In the same spirit, we as the industry leaders with the brightest engineers, contractors, and suppliers in the bridge industry, must ensure we understand what is on the horizon and ensure that we are meeting the challenges.

We have already started facing these challenges and are finding some opportunities. The recent events have forced us to move forward with our efforts to develop a webinar approach to our seminars and training sessions which have been well received. To me this has put vital information in the hands of many who would never have had the chance to attend one of our training classes in person. Although we are disappointed that we will be unable to hold our in-person annual convention this year, we are still working on plans to have a virtual event. We will miss the camaraderie that comes with the face to face encounters, but we hope that the opportunities to expand our exposure to others will ultimately broaden the industry's exposure to segmental bridges. We are still planning our 2021 event in Tucson and, until then, we hope everyone stays safe.

past.
present.
future.



The bridge features 24 scenic overlooks with educational plaques that memorialize U.S. conflicts and Veterans

This new, high-level bridge will be the first pre-cast open spandrel arch bridge in the U.S.

Design elements of the new two-lane bridge include handicap accessibility, 8-foot sidewalks and fishing piers on both sides of the Halifax River.

Veterans Memorial Bridge
Daytona, Florida
Client: Volusia County
WSP's Role: Designer

Question the existing *Imagine the impossible* Create the enduring

Clients partner with WSP to mobilize communities from coast to coast, drawing on our expertise in the planning, design and management of transportation infrastructure.

Find out what we can do for you.





Your Strongest Partner for Expansion Joint Systems

WBA has the experience to provide you with the assistance necessary to make your project a success. From custom engineering and specification to detail drawings and installation, we are there each step of the way to make sure your project exceeds the requirements.

Sarah Mildred Long Bridge
Wabo@Finger Joints

CONTENTS

DEPARTMENTS

- 1 Editorial**
- 5 Director's Corner**
- 6 Communication News**
Industry news about members, programs, research and development.
- 8 2018 Convention News**
Reflecting on our 2018 Convention.
- 10 2019 Convention News**
Reflecting on our 2019 Convention and looking forward to the 2020 Virtual Convention.
- 12 Committee News**
The latest updates from the ASBI Committees.
- 13 Segmental Construction Three Part Webinar Series**
~~Construction Practices Handbook for Concrete Segmental and Cable Support Bridges announcement~~
- 15 2020 Flexible Filler Certification Training Webinar Announcement**

FEATURE PROJECTS

- 17 US54 Canadian River Bridge**
A Community Outreach Opportunity
- 20 The New Ship Channel Bridge on the Sam Houston Tollway**
A precast segmental cable-stayed bridge for harris county toll road authority (HCTRA)
- 22 Alabama's Largest Transportation Project Renews Birmingham's Central Business District**
Aspire Magaziine reprint, Spring 2020.
- 27 Time-Saving Construction Techniques—I-59/I-20 Bridge Reconstruction**
Aspire Magaziine reprint, Spring 2020.

calendar

Due to the ongoing Coronavirus (COVID-19) situation, ASBI events are on hold until further information is provided regarding reopening of businesses and updates on travel restrictions by Federal and State governments. Please check the Events website for further information.

July 2020

S	M	T	W	T	F	S
			1	2	3	4
5	6	7	8	9	10	11
12	13	14	15	16	17	18
19	20	21	22	23	24	25
26	27	28	29	30	31	

1, 8 15

Segmental Construction Webinar Series

ASBI will be conducting a three part webinar series on Segmental Construction on July 1, 8 & 15. This will be companion training for the Construction Practices Handbook scheduled for ~~August 17-18~~ in Seattle, WA.

7

Flexible Filler Certification Training Webinar

FDOT/ASBI/PTI will be offering to those involved with upcoming post-tensioning projects in Florida.

20

Grouting Certification Training Webinar

Training necessary to understand and successfully implement grouting specifications for post-tensioned structures.

August 2020

S	M	T	W	T	F	S
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

17

2020 Construction Practices Seminar

The 2020 Construction Practices Seminar will be held at the Marriott Seattle Airport.

October 2020

S	M	T	W	T	F	S
				1	2	3
4	5	6	7	8	9	10
11	12	13	14	15	16	17
18	19	20	21	22	23	24
25	26	27	28	29	30	31

28

ASBI 32nd Annual Convention (Virtual)

Join us for our ~~one~~ day virtual 32nd Annual ASBI Convention.



ASBI 33rd Annual Convention and Committee Meetings

MARK YOUR CALENDAR

ASBI 33rd Annual Convention and Committee Meetings to be held at the The Westin La Paloma Resort & Spa November 8-10, 2021. Please see **Events** at www.asbi-assoc.org for further information.

Follow us on



Director's Corner



Gregg Freeby
Executive Director, ASBI
gfreeby@asbi-assoc.org

Greetings. I hope this newsletter finds you, and those close to you, healthy and staying safe.

I wanted to provide a brief update on what is happening at ASBI during this time, particularly since, as most of you are aware, we had to cancel our 2020 Convention. However, I strongly believe that ASBI will continue to provide value to our members.

We conducted our first ever virtual Grouting Certification Training by webinar on April 6th. This event drew ~~over 120~~ attendees. In fact, it was so successful we are working to make this an on-demand webinar in the coming weeks to allow individuals to complete the training at a time that works for their schedule.

We are also working on other educational opportunities that will be delivered online, including Flexible Filler Certification Training, a Segmental Bridge Construction Webinar Series, as a companion to our recently revised Construction Practices Handbook, and a Virtual Convention day on October 28th, to highlight some of the latest technology and innovations in our industry.

On the publications front, we are nearing completion on a number of resources including a "Segmental Bridge Planning and Design Manual," an "Operations and Maintenance Guidebook," and "Guidelines for Design and Construction of Segmental Bridges for Railway." We are also launching an effort to develop materials for conducting pre-construction workshops for segmental projects, segmental bridge owner training, access to a segmental bridge database, and updating the "Durability Survey." The "Annual Owner's Survey" will also be provided to you as a member benefit in the coming weeks.

You can see we have a lot happening despite the current situation. However, none of this happens without support from you and our member companies. I understand the uncertainty we are all facing but, I am certain of this, we will pull through this together, as an industry and as a country. Things will certainly be different in the future but one thing that will not be different is the need for strong industry partners to help you meet the challenges ahead. ASBI is here to help provide you with training, resources, as well as educational and networking opportunities.

Stay safe and please contact myself or Ingrid if you need anything.

Gregg Freeby

Follow us on



communication news



Grouting Certification Training

2019

There were 3 classes held in 2019:

February 12 held at the Rental Works Building in Birmingham, Alabama, with 31 attendees and 2 certified as Technicians.

April 8 held at the J.J. Pickle Research Campus in Austin, Texas, with 98 attendees and 9 certified as Technicians.

June 12 held at the Village of Logan Community Center, Logan, New Mexico, with 16 attendees.

2020

April 6 held as the first grouting training webinar, with 109 attendees and 8 certified as Technicians.

Moved and Have a New Address?

Please let us know if you have had an address change so we may update the information on the ASBI website as well as the mailing list. Don't forget to include new telephone, as well as e-mail address. You may send any updates to info@asbi-assoc.org.

New 2018-2020 ASBI Organizational Members

WE ARE PLEASED TO WELCOME THE FOLLOWING NEW MEMBERS TO ASBI:

ALLPLAN, INC.

10 North High Street, Suite 110
West Chester, PA 19380
(844) 425-5752

www.allplan.com

Jalpesh Patel,
Senior Technical Consultant

SOFISTIK NORTH AMERICA CORP.

17 Battery Place, Suite 1308
New York, NY 10004
(212) 488-1668

www.sofistik.com

Andres von Breymann,
Sales and Consulting

FHWA, EASTERN FEDERAL LANDS HIGHWAY DIVISION

21400 Ridgetop Circle
Sterling, VA 20166
(703) 404-6246

www.efl.fhwa.dot.gov

Hratch "Rich" Pakhchanian,
Bridge Branch Chief

SHUTTLELIFT

49 E. Yew Street
Sturgeon Bay, WI 54235
(920) 743-8650
FAX: (920) 743-1522

www.shuttlelift.com

Dan Reinholtz,
Industrial Sales Manager

STV INCORPORATED

225 Park Avenue S, 5th Floor
New York, NY 10003
(212) 777-4400
FAX: (212) 529-5237

www.stvinc.com

Jorge M. Suarez,
Vice President - National Bridge Tech
Director

SUPERIOR CONSTRUCTION COMPANY

7072 Business Park Blvd.
Jacksonville, FL 32256
(904) 703-9656

www.superiorconstruction.com

Pete Kelley,
President

New Academic Members

Bob McCullough

Purdue University

Hani Nassif

Rutgers University

Andrea Schokker

University of Minnesota - Duluth

Have news to share?
THEN TELL US!

Whether you have moved and need to update your information or have a story idea for an upcoming newsletter email us at info@asbi-assoc.org.



New Professional Members

Jordan Adams

JK Adams Engineering, PLLC

Don Bergman

COWI North America Ltd. - Canada

Yein Chow

PT ACSET Indonusa Tbk

Varun Dwivedi

DSI Bridgecon India Pvt. Ltd.

Nick Graczyk

Trumbull Corporation

Alex-Walter Gutsch

iBMB

Yidong He

Parsons

Kadir Serden Hekimoglu

Badeser Insaat Ltd. Sti.

Gregory Hunsicker

OnPoint Engineering and Technology LLC

Moinuddin Khan

AECOM Rico Lepore, Volkert, Inc.

Saeed Karimi

HNTB Corporation

Fredric Lausier

Lausier Infrastructure PLLC

Juan Mesa

ICC SAS

Benjamin Morris

Parsons

Ronald Pierce

DLN Limited Company

Jake Presken

Walsh Construction

Manukant Shrotriya

DSI Bridgecon India Pvt. Ltd.

Jose M. Simon-Talero

Torroja International LLC

Anoop Sugathan

VSL Middle East LLC

Yang Tan

GHD

Nathaniel Van Etten

WGI, Inc.

Vejarano Mojica

Roberto Enrique, Enerobeli, S.A.

Thomas Waits

HighSpans Engineering, Inc.

Douglas Whittaker

Michael Baker International



Interested in learning about the construction of segmental concrete bridges?

The 3rd Edition of the Construction Practices Handbook is available for **FREE download** at www.asbi-assoc.org/index.cfm/publications/publications. There have been **420+** downloads of this publication since it became available in July 2019.

This "How-To Handbook" was developed to provide guidance for construction of concrete segmental bridges. Although the segmental construction concept is generally very simple, the construction technology involved is, in numerous ways, more demanding than that required for other types of technology used in the industry. The use of concrete segmental bridge construction continues to grow throughout the United States and Canada. Increased use of this technology has led to a need to provide industry standard information for use by contractors, inspectors, quality control staff, and owners. In the interest of educating the industry, sharing best practices, and standardizing methods, this handbook is intended to provide a basic understanding of segmental construction technology. The overall goal is to facilitate the construction process, avoid common difficulties previously encountered, and reduce impacts to projects. This handbook is intended to be an industry guide aimed at focusing on specific aspects of the technology based on past experience.

New Student Members

Rutika Jawadwar

NICMAR National Institute of Construction Management & Research

Zachary White

University of Florida

New Transportation Official Members

Michael Barido

FHWA – Utah

Stefan Bilik

Illinois State Toll Highway Authority

Kimberly Coleman

New Mexico DOT

Mohamad Faraj

Illinois State Toll Highway Authority

Joe Hedges

California High-Speed Rail Authority

Xuejian Liu

Virginia DOT

Joel Villanueva

Chicago Transit Authority

Carrie Wagener

Chicago Transit Authority

convention news

2018 ASBI 30th Annual Convention

ASBI's 30th Annual Convention was held on November 6-7 at the Loews Chicago O'Hare in Rosemont, Illinois, with 322 attendees and 28 exhibitors.

THE 2018 BIENNIAL LEADERSHIP AWARDS WENT TO:

- **SEAN BUSH** – Outstanding Career Contributions Providing Project Management for Concrete Segmental Bridges
- **GREGORY HUNSICKER** – Outstanding Career Contributions for Technical Support of Concrete Segmental Bridges
- **BRETT PIELSTICK** – Outstanding Career Contributions Providing Leadership in Advocating the Benefits of Concrete Segmental Bridges
- **MAINE DEPARTMENT OF TRANSPORTATION AND JOYCE TAYLOR** – Outstanding Career Contributions in the Design, Construction, and Advancement of Concrete Segmental Bridges
- **BARTON NEWTON** – Outstanding Service and Leadership as ASBI President for 2017 and 2018
- **WILLIAM R. "RANDY" COX** – Outstanding Service and Leadership as ASBI Executive Director for 2008-2018



Pictured (left to right): Randy Cox, Brett Pielstick, Barton Newton, Gregory Hunsicker, Joyce Taylor, and Sean Bush. Photo courtesy of [PKS](#)

Thank You 2018 Convention Sponsors!

ASBI would like to thank the following organizational members for their sponsorship of the 30th annual Convention held in Rosemont, Illinois:

GOLD



PARSONS




SILVER

Bentley
Advancing Infrastructure



BRONZE





Thank You 2018 Convention Exhibitors!

BERD, s.a.

D.S. Brown

Deal/Rizzani de Eccher USA, Inc.

Doka. The Formwork Experts.

DYWIDAG Systems International
USA, Inc. (DSI)

Enerpac

Epoxy Interest Group of CRSI

Euclid Chemical Company

F&M MAFCO, Inc.

Freyssinet, Inc.

Fugro Loadtest

General Technologies, Inc.

Hilman Rollers

LARSA, Inc.

LUSAS Bridge Analysis Software

mageba USA LLC

PERI Formwork Systems, Inc.

Precision-Hayes International

R.J. Watson, Inc.

RS&H, Inc.

Schwager Davis, Inc.

Shuttlelift

Sika Corporation

SOFISTIK AG

Structural Technologies VSL

Sumiden Wire Products Corporation

Williams Form Engineering Corp.

Wowjoint Holdings

Photos Courtesy of [222](#)

convention news

2019 ASBI Annual Convention

The 2019 ASBI Annual Convention was held on November 5-6 at Disney's Contemporary Resort in Orlando, Florida. The Convention was well attended with 310 registrants and 29 exhibitors.

THE 2019 BIENNIAL BRIDGE AWARDS OF EXCELLENCE WENT TO:

- **Marc Basnight Bridge**, Outer Banks, NC
- **Lesner Bridge**, Virginia Beach, VA
- **Bayonne Bridge**, NY / NJ
- **Sarah Mildred Long Bridge**, Kittery, ME
- **I-49 / I-220 Interchange Segment K**, Caddo Parrish, LA
- **St. Croix Crossing**, MN / WI
- **I-91 Brattleboro Bridge**, Brattleboro, VT



Photo Courtesy of [Group Photo Inc.](#)

Thank You 2018 Convention Sponsors!

ASBI would like to thank the following organizational members for their sponsorship of the 30th annual Convention held in Rosemont, Illinois:

GOLD



SILVER



BRONZE





Thank You 2019 Convention Exhibitors!

CMC - MMFX Technologies

D.S. Brown

Deal / Rizzani de Eccher USA, Inc.

Doka. The Formwork Experts.

DYWIDAG-Systems International

Enerpac

Euclid Chemical Company

F&M MAFCO, Inc.

Freyssinet, Inc.

FUCHS Lubricants Co.

Fugro Loadtest

General Technologies, Inc.

Hilman Rollers

Icon Forming Solutions

LARSA, Inc.

LUSAS Bridge Analysis Software

mageba USA LLC

PERI Formwork Systems, Inc.

R.J. Watson, Inc.

RS&H, Inc.

Schwager Davis, Inc.

Shuttlelift

Sika Corporation

SOFiSTiK AG

Structural Technologies VSL

Sumiden Wire Products Corporation

Trompler Fluid Power, Inc.

Watson Bowman Acme

Williams Form Engineering Corp.



Photos Courtesy of [PERI](#)

We hope you will join us
for our one day virtual 32nd
Annual Convention on
October 28, 2020.

Please see **Events** at www.asbi-assoc.org
for further information and online registration.

committee news

Have ideas worth sharing?

New ideas are always important, contact a committee member and get involved today.



COMMUNICATIONS & MEMBERSHIP

Mark McRobie, Chair
RS&H



As a result of the Strategic Plan update approved at the annual meeting of the Board of Directors on November 4, 2019, the Communications and Membership Committees have been merged into a single committee. This move is expected to reduce the overlap between the two previous committees. Mark McRobie, with RS&H, has taken on the role as Committee Chair.

This now combined committee is working on a Roadmap for Social Media Campaign. The annual Owner's survey is complete, and the committee is working to publish the results.

A contract has been executed with Dr. Andrea Schokker, with the University of Minnesota Duluth, to take over the creation of the ASBI Segmental Database and Durability Report. Gregg Freeby will lead a small steering committee comprised of Keith Ramsey and Brett Pielstick to support this effort. More on this effort will be provided in future newsletters.

EDUCATION

Patrick Malone, Chair
PCL Civil Constructors, Inc.



Ken Price continues to do an outstanding job leading the development of the new ASBI Planning and Design Manual. A first draft is expected to be finished this fall. After that a small team of subject matter experts will do an integrated review of the entire document. Please contact Ken Price (Kenneth.Price@wsp.com) or the ASBI office (info@asbi-assoc.org) if you, or someone you know is interested in this opportunity.

The committee is also continuing the development of an Operations and Maintenance Manual under the leadership of Brett Pielstick. A first draft of this document is expected this fall as well.

The 3rd Edition of the Construction Practices Handbook was published this past June. Electronic copies can be downloaded directly from the ASBI website at: www.asbi-assoc.org/index.cfm/publications/handbook-download.

The Construction Practices Workgroup, under the leadership of Tim Barry, has put together a three-part webinar series on Segmental

Bridge Construction to be conducted on July 1, 8 & 15th. See details on this webinar series elsewhere in this newsletter.

The Grouting Work Group, currently under the leadership of Greg Hunsicker, successfully provided the annual Grouting Certification Training by webinar on Monday, April 6, 2020. This was in response to the travel restrictions due to the COVID-19 pandemic and drew participants from all over the U.S., Canada, and even Israel! There were over 100 individuals that completed the training. An on-demand rebroadcast of this web training will be available in late July. Check the ASBI website for registration information.

TECHNOLOGY & INNOVATION

Greg Shafer, chair
~~Parsons is the chair of this committee.~~



There are a lot of activities happening in the various subcommittees within this committee. For example, John Dunham is chairing the Construction Subcommittee and they are looking at what's happening with flexible fillers, joints, and CFRP for segmental.

Kent Montgomery's Design Subcommittee is looking at the latest fib creep models, recommended changes to the segmental specific AASHTO LRFD articles, thermal gradient design aspects, and continuing to support T-10.

Jeff Pouliotte's M&O Subcommittee authored a segmental load rating problem statement that was recently approved by AASHTO for funding. This NCHRP research project is expected to result in higher load ratings for older segmental bridges that will improve mobility. The M&O Subcommittee has identified and tracked 4 recently completed research projects and 8 proposed or on-going research projects, primarily focused on evaluation of existing bridge condition and mitigation. FDOT has an ongoing research project to develop a portable magnetic flux prototype to measure section loss for internal tendons (based on a German design), and has completed the second phase of a research project to identify tendon loss using impedance based detection.

Sarah Mildred Long Bridge
Photo Courtesy of FIGG

Lesner Bridge
Photo Courtesy of RS&H



Segmental Construction Three Part Webinar Series

July 1, 8, 15, 2020

Taken from the Construction Practices Handbook for Concrete Segmental and Cable-Supported Bridges. We are pleased to announce ASBI will be hosting a new three-part webinar series on Segmental Bridge Construction. In this course, participants will receive in-depth instruction on precast and cast-in-place concrete segmental bridge construction. This learning opportunity is a companion to our recently updated Construction Practices Handbook for Concrete Segmental and Cable-Supported Bridges.

The first session provides an introduction and overview of the segmental construction methods. The second session goes into more advanced concepts including production, handling, transportation, and erection of precast segments. In addition, advanced concepts around segmental geometry control, post-tensioning details and QC/QA inspection will be covered. We conclude the series with project examples. In this session we tie everything together with in-depth studies of two recent projects, one using precast span-by-span construction and the other using cast-in-place balanced cantilever construction.

Participants will receive a much deeper understanding of the technical aspects of concrete segmental construction methods. In addition, they will receive a certificate of completion for 6 professional development hours certified by Registered Continuing Education Program (RCEP).

Details available at:

<https://www.asbi-assoc.org/index.cfm/ConstructionPracticesWebinar>



I-91 Brattleboro Bridge
Photo Courtesy of
Richard Tremblay

Follow us on



Segmental Bridge Construction


Three Part Webinar Series

July 1, 8, and 15, 2020

July 1 1:00 p.m.—3:00 p.m. EDT	Session 1—Introduction 1:00 —1:05 WELCOME AND COURSE INTRODUCTION 1:05 —1:30 MODULE 1—SEGMENTAL OVERVIEW 1:30—2:15 MODULE 2—CAST-IN-PLACE SEGMENTAL CONSTRUCTION 2:15—3:00 MODULE 3—PRECAST SEGMENTAL CONSTRUCTION SPAN-BY-SPAN ERECTION BALANCED CANTILEVER ERECTION
July 8 1:00 p.m.—3:00 p.m. EDT	Session 2—Advanced Concepts 1:00 —2:00 MODULE 4—PRECAST SEGMENTAL CONSTRUCTION (CONTINUED) PRODUCTION OF PRECAST SEGMENTS EQUIPMENT FOR HANDLING, TRANSPORTING AND ERECTING PRECAST SEGMENTAL BRIDGES 2:00 —3:00 MODULE 5—SEGMENTAL DETAILS GEOMETRY CONTROL POST-TENSIONING DETAILS INSPECTION—QC/QA
July 15 1:00 p.m.—3:00 p.m. EDT	Session 3—Project Examples 1:00 —2:00 I-59/I-29 BRIDGE REPLACEMENT 20/180 (PRECAST SPAN-BY-SPAN) 2:00 —3:00 CANADIAN RIVER BRIDGE (CAST-IN-PLACE BALANCED CANTILEVER)

Professional Engineering Development Hours

Participants will receive a certificate of completion for 6 professional development hours certified by Registered Continuing Education Program (RCEP) only if all 3 sessions are completed.



Photos courtesy of FDOT.

July 7, 2020 Webinar

The training is required for the foremen, technicians, as well as quality control inspectors involved with post-tensioning tendon flexible filler injection in Florida.

For information regarding the requirements for the use of flexible fillers on Florida DOT projects, check:

www.fdot.gov/structures/structuresmanual/currentrelease/structuresmanual.shtm

Sponsored by



Florida Department of Transportation



**FLEXIBLE FILLER CERTIFICATION TRAINING
AGENDA**

Tuesday, July 7, 2019

All Times Are EDT

Morning

7:30 a.m. – 8:00 a.m.	Webinar Open for Early Connection and Troubleshooting	
8:00 a.m. – 8:15 a.m.	Welcome, Webinar Basics Presentation	Gregg Freeby ASBI
8:15 a.m. – 8:45 a.m.	Module 1 – Introduction	Sam Fallaha FDOT
8:45 a.m. – 9:30 a.m.	Module 2 – FDOT Policy / Specifications/ Standard Plans	Jacqui Petrozzino-Roche FDOT
9:30 a.m. – 10:00 a.m.	Module 3 – Flexible Filler Materials	Natassia Brenkus The Ohio State University
10:00 a.m. – 10:15 a.m.	BREAK	
10:15 a.m. – 10:45 a.m.	Module 4 – Details and Installation of Hardware	Teddy Theryo FDOT
10:45 a.m. – 11:45 a.m.	Module 5 – Equipment Review	Gregory Hunsicker OnPoint Engineering & Technology
11:45 a.m. – 12:45 p.m.	LUNCH	

Afternoon

12:45 p.m. – 2:45 p.m.	Module 6 – Procedure for Injection	Will Potter FDOT
2:45 p.m. – 3:00 p.m.	BREAK	
3:00 p.m. – 3:30 p.m.	Module 7 – Safety Review	David Wagner FDOT
3:30 p.m. – 5:00 p.m.	Module 8 – Field Examples and Lessons Learned	Thomas Woods HNTB Robert Bennett RS&H
5:00 p.m. – 6:00 p.m.	Exam	
6:00 p.m.	END OF WEBINAR	

Exams Due to ASBI Office via Email by 7:00 p.m.

Send to: info@asbi-assoc.org

project news



Caption to come. (Photo courtesy of ??.)

US54 Canadian River Bridge

A COMMUNITY OUTREACH OPPORTUNITY

Located in northeastern New Mexico in the village of Logan, this project is the state's first cast-in-place segmental bridge. The New Mexico Department of Transportation (NMDOT) is replacing the existing US 54 steel deck truss bridge over the Canadian River. The US 54 corridor is the main trucking corridor from Chicago to El Paso with over 50% truck traffic. US 54 also provides access in this area to Ute Lake State Park, the second largest lake in New Mexico, which is popular with water and fishing enthusiasts.

An alignment study with public input led to the selection of a cast-in-place segmental bridge to minimize impacts to the Canadian River, the river's protected inhabitants, and the surrounding wetlands. The long-span design is constructed primarily from above with limited access in the deep ravine. The bridge measures 43'-0" in width, with a span configuration of 200'-325'-210' along a constant horizontal curve. The bridge measures 43'-0" in width, with a span configuration of 200'-325'-210' along a constant horizontal curve. The box girder depth varies from 18'-0" at the piers to 8'-0" at mid-span and the abutments.

The project team was led by New Mexico DOT, with support from the Federal Highway Administration. Design, as well as Construction Engineering Support, was provided by **Jacobs Engineering** with **Malcolm International** leading the segmental construction as a subconsultant to the prime contractor Fisher, Sand, and Gravel. ASBI provided additional support and guidance during the project with on-site Grouting Certification Training for the US54 project team. This collaborative team worked seamlessly together to accomplish the exciting project in this rural and beautiful location.

"THIS IS YOUR BRIDGE"

During segmental construction, NMDOT, **Jacobs**, and **Malcolm** came together to provide two interactive presentations (K-5th and 6th-12th) for the students of the Logan School District. As the bridge was in construction in this small town for over a year at the time of the presentation, the students and teachers were brimming with questions. It was a wonderful opportunity to provide information, demonstrate career paths in engineering and trade, and help the students gain ownership of their exciting bridge. After the presentations, the kids had a chance to get hands-on and learn more with a tendon anchorage assembly, rebar cage, concrete cylinders, safety PPE, and design drawings.

Segmental cantilever construction is completed with final span closures anticipated to be completed in June 2020.

OWNER
New Mexico
Department of Transportation

DESIGNER AND OWNER'S ENGINEER
Jacobs Engineering

CONTRACTOR
Fisher Sand and Gravel

SEGMENTAL CONTRACTOR
Malcolm International

CONSTRUCTION ENGINEERING
McNary Bergeron & Associates

FORM TRAVELERS FOR CAST-IN-PLACE SEGMENTS
Schwager Davis, Inc.

BEARINGS
D.S. Brown Company

EXPANSION JOINTS
Watson Bowman Acme

PREPACKAGED GROUT
US Spec NA Grout

An alignment study with public input led to the selection of a cast-in-place segmental bridge to minimize impacts to the Canadian River



Caption to come.
(Photo courtesy of ??.)



FLORIDA

VIRGINIA

NORTH CAROLINA

NEW JERSEY

MAINE



FLORIDA

MINNESOTA

TENNESSEE

UTAH

MAINE/NEW HAMPSHIRE

TEXAS



FLORIDA

NEW YORK

OHIO

DELAWARE

VERMONT

**A FOCUS ON BRIDGES
FOR OVER 42 YEARS** →
Concrete segmental bridge design
through construction engineering
and inspection services



CREATING BRIDGES AS ART®

www.figgbridge.com | 1 800 358 3444



HAWAII

TEXAS

FLORIDA

NORTH CAROLINA

COLORADO

GEORGIA



OKLAHOMA

MISSISSIPPI

VIRGINIA

ALABAMA

MINNESOTA/
WISCONSIN



WASHINGTON

SOUTH CAROLINA

NORTH DAKOTA

PENNSYLVANIA

TEXAS

COLORADO



Doing **BIG** Things for 75 Years

AT F&M MAFCO WE ARE CELEBRATING 75 YEARS AS A COMPANY DOING BIG THINGS. AS WE REFLECT ON THOSE YEARS, WE CONTINUE TO EVOLVE WHILE MOVING INTO A NEW ERA AT FULL CAPACITY.

EQUIPMENT AND TOOLING RESOURCES, RENTAL SOLUTIONS AND EFFICIENCY INNOVATIONS FOR CAPITAL CONSTRUCTION, INFRASTRUCTURE & MAINTENANCE PROJECTS, AND INDUSTRIAL SUPPLY.

BIG



Toll-Free: 1.800.333.2151 | www.fmmafco.com 



ASBI 33rd Annual Convention and Committee Meetings

MARK YOUR CALENDAR

ASBI 33rd Annual Convention and Committee Meetings to be held at the The Westin La Paloma Resort & Spa November 8-10, 2021. Please see **Events** at www.asbi-assoc.org for further information.

We hope you will join us for our one day virtual 32nd Annual Convention on October 28, 2020.

Please see **Events** at www.asbi-assoc.org for further information and online registration.





A completed precast segment is lifted from the long-line casting machine using a rail gantry crane.

OWNER
Harris County Toll Road Authority

DESIGNER
FIGG

CONTRACTOR SHIP CHANNEL CONSTRUCTORS
a Joint Venture of
Traylor Bros., Inc. and
Zachry Construction

CONSTRUCTION ENGINEERING SERVICES
T.Y. Lin International

CONSTRUCTION ENGINEERING INSPECTION
HNTB Corporation

FORMWORK FOR PRECAST SEGMENTS
DEAL

ERECTION EQUIPMENT
NRS

POST-TENSIONING MATERIAL
Dywidag Systems International, USA, Inc.

STAY CABLE MATERIALS
Dywidag Systems International, USA, Inc.

BEARINGS
D.S. Brown Company



Flying a completed rebar cage to the long-line mold.

The New Ship Channel Bridge on the Sam Houston Tollway

A PRECAST SEGMENTAL CABLE-STAYED BRIDGE FOR HARRIS COUNTY TOLL ROAD AUTHORITY (HCTRA)

Construction is underway on the New Ship Channel Bridge in Houston, Texas for the Harris County Toll Road Authority. The 2,720' (1,320' main span) signature cable-stayed bridge consists of twin 81'-9" wide and 12' deep precast concrete segmental superstructures that will support four lanes of traffic in both the southbound and northbound directions. The on-site casting yard adjacent to the existing bridge is currently producing match-cast segments

using two sophisticated long-line formwork systems. Diagonal concrete struts, located within the box girder interior, are precast at the casting yard and tied into each segment's rebar cage in one of four jigs. After the pre-tied rebar cage and struts are lifted into the long-line casting machine, the movable bulkhead is surveyed and final QA/QC checks are performed. Concrete is batched and delivered to the forms from a dedicated concrete batch plant near the project site. The long-line casting machine produces segments in continuous casting groups of up to 14 segments with a total length of almost 130'. Upon completion of the casting group, the segments are removed from the long-line molds using an overhead rail gantry crane and then transported to the segment storage area with a 160-ton capacity straddle crane. The adjacent storage yard is large enough to accommodate more than 500 precast segments.

The 2,720' (1,320' main span) signature cable-stayed bridge consists of twin 81'-9" wide and 12' deep precast concrete segmental superstructures that will support four lanes of traffic in both the southbound and northbound directions.

ASPIRE

THE CONCRETE BRIDGE MAGAZINE

Reprinted from ASPIRE® magazine

SPRING 2020

www.aspirebridge.org

Interstate 59/Interstate 20 Bridge Reconstruction *Birmingham, Alabama*


HARLEM RIVER DRIVE BRIDGE OVER EAST 127TH STREET
New York, New York

GENESEE AVENUE VIADUCT
La Jolla, California

Presorted Standard
Postage Paid
Lebanon Junction, KY
Permit No. 567

Alabama's Largest Transportation Project Renews Birmingham's Central Business District

by Lloyd Pitts, Volkert Inc., Eric Johnson, Corven Engineering Inc., and William (Tim) Colquett, Alabama Department of Transportation



Aerial view of the Phase III segmental bridge site, shown here in magenta. Five miles of segmental box girders with a total of 2316 segments were erected in only 217 days, and the bridges reopened to traffic ahead of schedule. Figure: Volkert Inc.

For nearly 50 years, millions of motorists have traveled the Interstate 59/Interstate 20 (I-59/I-20) from Meridian, Miss., to Birmingham, Ala. Once the interstates reach Birmingham, a city with a legacy built on steel and iron, they are now supported by elevated concrete structures over the downtown area.

Serving Birmingham's central business district (CBD), this artery has the highest rate of traffic flow in the state of Alabama. Built in 1973, the original

elevated structures were designed for 80,000 vehicles per day. Current traffic exceeds 160,000 vehicles per day, and traffic forecasting suggests that this route may be subject to over 225,000 vehicles per day by 2035.

As a result of the age and heavy use of the facility, the bridge decks had begun to deteriorate, often requiring costly repairs that resulted in lane closures. The original bridges featured left-lane entrance and exit ramps, with minimal

or no shoulders. Three of these ramps were considered outdated and forced motorists to make unanticipated and unsafe lane crossings, sometimes resulting in accidents that forced traffic slowdowns or stoppages (see the State article on Alabama in the Spring 2019 issue of *ASPIRE*[®]).

Rebuilding the Bridges

Considering the safety concerns, traffic congestion, and maintenance issues, the Alabama Department of Transportation

profile

INTERSTATE 59/INTERSTATE 20 BIRMINGHAM CENTRAL BUSINESS DISTRICT BRIDGES / BIRMINGHAM, ALABAMA

BRIDGE DESIGN ENGINEERS: Volkert Inc., Mobile, Ala. (prime consultant, substructure and foundations); Corven Engineering Inc., Tallahassee, Fla. (segmental superstructure)

CONTRACTOR'S CONSTRUCTION ENGINEERS: McNary-Bergeron & Associates, Broomfield, Colo.; Infrastructure Consulting & Engineering, Columbia, S.C.

PRIME CONTRACTORS: Johnson Bros. Corp., a Southland Company, and Oscar Renda Contracting Inc. Joint Venture, Roanoke, Tex.

(ALDOT) deemed this infrastructure functionally obsolete and determined that immediate action was required. Multiple options were considered, including burying the interstates, rerouting the corridor, or simply redecking the existing bridges. Some of these options were projected to take 20 years and billions of dollars to complete, and yet they would not adequately solve the corridor's problems.

ALDOT determined that the best course of action would be to replace some CBD bridges and widen others, with the interstates completely shut down during construction. Compared to long-term construction phasing, this plan required the shortest turnaround time and thus would cause the least disruption to the traveling public.

ALDOT engaged a single consulting firm team to provide the engineering design and construction inspection services for the \$710 million megaproject. The project, with 36 bridge sites for either new bridges or widening of existing bridges, was separated into four bid packages—Phases A, I, II, and III. The concrete bridges for the project totaled 14.3 miles of precast, prestressed concrete girders and 5 miles of segmental box girders. The \$440 million Phase III project included the segmental box girder bridges.

Work on the Phase III CBD bridge replacement project was performed in concert with many other improvements in the CBD region to improve traffic movements, replace or modernize existing facilities, and revitalize the downtown experience for the citizens and visitors of Birmingham.

Substructure Challenges and Solutions

To minimize the impact of the project on downtown Birmingham, a diverse



A typical span after erection of the four lines of box-girder segments. A longitudinal closure pour about 3 ft 6 in. in width was used to join the segments for each of the two bridges. The completed eastbound and westbound structures are separated by a 6 in. gap. Photo: Volkert Inc.



Falsework towers were used to support segments during erection. Photo: Volkert Inc.

ALABAMA DEPARTMENT OF TRANSPORTATION, OWNER

POST-TENSIONING CONTRACTOR: Structural Technologies, Columbia, Md.

CASTING MACHINES AND ERECTION SYSTEM: Structural Technologies, Columbia, Md.

BRIDGE DESCRIPTION: 6500-ft-long precast concrete segmental box-girder bridges with 2316 segments total

STRUCTURAL COMPONENTS: Five miles of precast concrete segmental box girders, 172 spans, and 2316 segments, precast concrete piers

SEGMENTAL BRIDGE CONSTRUCTION COST: \$195 million



A precast concrete pier cap with fluted aesthetic detailing is erected on a column element. Segments are connected using grouted couplers. Photo: Volkert Inc.

business hub with a bustling food and art scene, only 14 months of full interstate closure were allowed for construction; also, access to certain CBD public venues was required throughout the project. Additional challenges included limited right-of-way, utility conflicts, varying geotechnical conditions along the project corridor, and limited vertical clearance under the existing structures to perform foundation work before the interstates were closed.

Aesthetics were a priority for ALDOT, so the design team decided to use single-column piers under each segmental girder line. The piers are accented with vertical fluted lines in the near and far faces, and the pier caps flare out at the top to complement the sloping lines of the segmental girders. The contractor elected to precast the piers as two separate pieces, columns and caps, for faster construction. The reinforcement for the pier sections was made continuous with grouted couplers. This allowed the piers to be constructed efficiently once the demolition and removal operations for the existing structures were completed.

The first two-thirds of the project had sound rock for foundation design. Near 22nd Street North, there was a



AESTHETICS COMMENTARY

by Frederick Gottemoeller

Faced with a request for a viaduct that would “revitalize the downtown experience for the citizens and visitors of Birmingham,” the project’s designers thought creatively about the appearance of the space below the structure. Such spaces are often dark and uninviting, filled with haphazardly parked cars and drifting waste paper, depressing the activities around them. Improving the appearance of such a space requires conceiving of it as a huge outdoor “room,” with the superstructure as its ceiling and the bridge piers articulating the room-like impression.

The attractiveness of this “room” depends, first of all, on long, uninterrupted sight lines in both the transverse and longitudinal directions, so that the whole area can be seen and understood

at once, so that it can be organized for uses beyond parking, such as farmers markets and art fairs, and so that there are few opportunities for concealment. The concrete box girders contribute to this goal by minimizing the number of pier legs both longitudinally (by allowing relatively long spans) and transversely (by requiring only four pier legs per pier line). The thin piers also avoid a problem that sometimes results when designers are asked to provide a structure with architectural grandeur: They attempt to do so with physical mass and “architectural” detail. The result can be an agglomeration of massive piers with nonstructural decorative details. Thus, an individual looking along the bridge sees the piers line up one behind the other, visually filling the “room” with concrete. In contrast, the

thinness of the Birmingham piers keeps the long views open, and the “room” inviting. The piers’ only architectural details are the closely spaced vertical grooves that visually reinforce their thin appearance.

The concrete box girders also keep the longitudinal views simple. The sight lines are not blocked by transverse pier caps, and there are no braces or diaphragms to catch the eye. The wide spacing between box webs means that light can reach to the underside of the deck slab, and the whole underside of the bridge stays bright. Finally, a reflective white coating on the underside of the structure keeps light bouncing around the “room,” meaning the space is brighter during the day and easier to light at night.

It is heartening to see this high level of aesthetic quality achieved within the discipline of accelerated bridge construction. Birmingham has met its schedule while achieving an “aesthetically pleasing area for public events”—all at the same time.



Erection of a precast concrete box-girder segment on temporary support towers for the first span of the central business district bridges. Photo: Volkert Inc.

geological shift, and the last one-third of the project had karst limestone conditions. In areas with sound rock, the footings used either drilled shafts or micropiles. In karst conditions, the foundations used steel H-piles with driving shoes. The span layouts for the project considered existing foundation locations and minimized conflicts for the new substructure locations.

Prior to the closure of I-59/I-20, the contractor built as many of the footings as possible. Because of the limited vertical clearance, low-overhead equipment was used to install the drilled shafts, micropiles, and steel H-piles. The footings were then covered with fill to protect them during the demolition of the existing overhead structures.

Creating the Superstructure

When ALDOT decided to allow I-59/I-20 to be closed for 14 months of construction, the designers had to find a design solution that could be achieved within this tight schedule. The contractor was allowed to fully close the interstates for 14 months without penalty, and would be awarded bonuses of \$250,000 per day for finishing early, with total bonuses capped at \$15 million. However, at the end of the 14-month window, penalties would be assessed at a rate of \$250,000 per day, with no cap. These time constraints led the design team to choose a precast

concrete segmental superstructure for Phase III of the project.

Because of the limited right-of-way and the need to preserve existing buildings along the project corridor, the replacement bridges were built within the same footprint as the original bridges. The eastbound and westbound structures are each approximately 6500 ft in length and are separated by a 6 in. gap.

Each bridge comprises twin precast concrete segmental box girders, and every mainline bridge includes entrance and exit ramps. Along the transition regions for these ramps, the mainline structures comprise three segmental box girders.

With a total deck area of over 1 million square feet, the bridges are composed of 172 spans, with nominal lengths of 165 ft. There are 2316 precast concrete segments, with typical segment lengths between 11 ft 6 in. and 12 ft 6 in. The overall box-girder segment depth is 9 ft, with an additional ½ in. of sacrificial deck surface that was milled to achieve a smooth deck surface after segment erection.

The lane configurations for the bridges vary along the project corridor from four to six lanes, resulting in a variation of out-to-out bridge width. To accommodate this variation in overall bridge width, the individual box girders were categorized

into three groups: 33 ft 6 in. wide for the four-lane configuration; 39 ft 6 in. wide for the five-lane configuration; and 45 ft 6 in. wide for the six-lane configuration. Individual box girders were joined with a longitudinal deck closure strip approximately 3 ft 6 in. wide to make up the total deck width for one bridge. To facilitate the precasting operations, all box girders used a constant core dimension with only the wing lengths varying.

The top slab of each box-girder segment was transversely post-tensioned with four-strand tendons that anchor at the end of each segment wing. To accommodate the variation in the width of the top slab, two transverse post-tensioning spacings were used: four tendons per segment for box-girder widths of 39 ft 6 in. or less, and five tendons per segment for box-girder widths greater than 39 ft 6 in.

The longitudinal post-tensioning in each box-girder span consists of external draped tendons. Eight permanent tendons (four per web) were anchored at the ends of the spans in the pier segment or expansion-joint segment diaphragms. The longitudinal post-tensioning tendon sizes vary depending on demand, with hardware sized to accommodate a maximum of 22 strands per tendon. Wider sections with longer span lengths feature one additional 12-strand tendon per web, anchored



The area beneath the completed mainline spans after painting. City officials intend to use this area for public events.
Photo: Johnson Bros.

at the deviation diaphragms. Each span also includes hardware to accommodate two 12-strand future post-tensioning tendons. Project-specific specifications for the installation and grouting of the post-tensioning tendons included many aspects of the *PTI/ASBI M50.3-12 Guide Specification for Grouted Post-Tensioning*.¹ (A newer version of this specification is now available—see the Concrete Bridge Technology article in the Summer 2019 issue of *ASPIRE*.)

Advantages of the Precast Concrete Segmental Design

The precast concrete segmental bridge design was chosen for several reasons stemming from ALDOT's decision to completely shut down I-59/I-20 during construction. In particular, the selected design minimized the time of interstate closure by using off-site fabrication and rapid construction methods.

The casting yard was located approximately 4 miles from the project, which allowed efficient transport of the precast concrete segments to the

construction site for placement. This expedited the construction process compared to the traditional methods for building bridges. By the time the interstates were closed to traffic, approximately 1000 of the 2316 segments were already cast and ready for erection.


Segment Erection

The original design assumed a traditional span-by-span erection method, with all precast concrete segments supported by longitudinal erection trusses. The contractor elected to use a unique technique, for which the design was verified, erecting each precast concrete segment within a span on individual shoring towers. This erection technique meant the contractor could work on as many as eight spans at any given time and facilitated nonlinear construction. The method proved to be successful, with all 2316 segments (172 spans) erected in only 217 days. (For more details on this technique, see the Concrete Bridge Technology article on page 30 of this issue of *ASPIRE*.)

The Finish Line

The challenges and time constraints of this project proved how beneficial precast concrete segmental bridge design and construction can be. The I-59/I-20 CBD bridges reopened to traffic ahead of schedule on January 17, 2020, with a closure of only 12 months compared with the 14 months allowed in the contract.

Reference

1. Post-Tensioning Institute (PTI) and American Segmental Bridge Institute (ASBI). 2012. *PTI/ASBI M50.3-12: Guide Specification for Grouted Post-Tensioning*. Farmington Hills, MI: PTI. 

Lloyd Pitts is vice president and chief bridge engineer with Volkert Inc. in Mobile, Ala., Eric Johnson is a bridge engineer with Corven Engineering Inc. in Tallahassee, Fla., and William (Tim) Colquett is the state bridge engineer for the Alabama Department of Transportation in Montgomery.

Time-Saving Construction Techniques – I-59/I-20 Bridge Reconstruction

By Robert W. Sward, Structural Technologies LLC

Since the 1970s, precast concrete segmental bridge construction has been used throughout the United States and many other parts of the world. Precast concrete segmental bridges are highly durable structures and may have predicted service lives greater than 100 years. As with most other forms of precast concrete construction, precast concrete segmental bridges can be constructed relatively quickly and allow the contractor to take advantage of innovative construction techniques. The recently completed Interstate 59/ Interstate 20 (I-59/I-20) elevated bridge replacement project in Birmingham, Ala., showcases the benefits of precast concrete segmental construction (see the Project article on page 10 of this issue of *ASPIRE*[®]). This replacement project is one part of the \$750 million Alabama Department of Transportation (ALDOT) reconstruction program for the I-59/I-20 corridor.

Strategies to Achieve an Aggressive Timeline

To minimize the impact of construction on the community, ALDOT opted to shut down the corridor to complete the replacement of the elevated structures in one phase. The maximum construction duration established in the contract was 14 months, but the contractor could maximize early-completion incentives by completing construction in 12 months. Constructing the replacement in multiple phases would have extended the project duration for several years. In May 2017, ALDOT awarded Johnson Bros. Corporation the \$474.7 million contract for the I-59/I-20 bridge replacement project. This contract included a substantial bonus for early completion and unlimited liquidated damage penalties for late completion. To successfully complete this project and



Precast concrete column in form with core form being extracted. Photo: Johnson Bros.

minimize schedule risk, Johnson Bros. implemented the following strategies.

Advance Work Beneath the Existing Bridge

The contractor decided to complete many of the new foundations and footings prior to shutting down the interstates for demolition. They used a combination of driven H-piles and drilled shafts and, where there was limited head room, implemented micropiles to install the new foundations around and beneath the existing elevated roadway.

Precasting the Concrete Substructures

By precasting 160 pier cap and column substructure elements, the contractor was able to benefit from the nearby casting yard and minimize critical path activities. Delivering and assembling precast concrete elements proved to be much faster than conventionally forming and pouring variable-height piers in place.

Use of Custom Shoring Towers in Precast Concrete Segment Erection

In the original design, the use of longitudinal erection trusses was assumed. This is a linear method of segmental construction in which the erection truss is launched to the next span only after one span is fully erected. To meet an incentive-maximizing 12-month construction schedule using this method, Johnson Bros. would have needed a minimum of six launching trusses working concurrently. This linear method of erection would have been risky because if the erection of a particular span could not progress in sequence, the contractor lacked the flexibility to quickly move the erection equipment to another work area.

Working with Structural Technologies/VSL, Johnson Bros. elected to use custom shoring towers to support the precast concrete segments during segment erection in lieu of longitudinal erection trusses. This method reduced schedule risk



Precast concrete column segments in storage. Note the extended column reinforcement and grout sleeves that are visible on the ends of the segments. Photo: Johnson Bros.

by providing the contractor the flexibility to deploy erection crews and equipment as needed to maintain the construction schedule, while allowing the use of more traditional construction equipment (cranes) for erection of the segments. If one particular span could not be erected in series, the crew and erection equipment could be redeployed to another area of the project. This method also allowed flexibility in sequencing the work.

The shoring towers supplied were custom designed and fabricated for this project. Shoring towers were preassembled at the fabricator's facility to ensure proper fit-up. The tower bases were fitted with screw jacks for vertical adjustments, and the tops were telescopic and fitted with jacking boxes. The main elements of the shoring towers were color-coded to be easily identified by field crews for their proper locations. Approximately 127 individual shoring towers were provided, which allowed the contractor to work

on up to eight fronts at one time. To ensure that underground utilities near the towers would not be damaged by the construction loads imparted by the shoring towers, a foundation load analysis was performed.

Three-Dimensional Modeling

During the bid phase, a virtual three-dimensional model of the entire project was developed. Using this model, each bridge span was studied to confirm that it could be erected using the proposed shoring method. The study revealed that several spans would require special portal frames and/or sliding of the segments due to crane access limitations and ground conflicts, such as railroad tracks and streets that could not be closed.

Minimizing the Number of Segments

The length of typical and deviator segments was increased from 10 ft to 12 ft, which reduced the number of



Reinforcing bar cage with transverse tendons being installed into forms. Photo: Johnson Bros.

segments to cast, store, transport, and erect by about 400 segments. The team had to account for subsequent increases in segment weights and ensure that limits would not be exceeded for cranes, shoring, and hauling.

Dedicated Batch Plant

A project-dedicated batch plant was installed in the casting yard, including a quality-control lab. The dedicated batch plant ensured consistent delivery and quality of concrete as needed for both the jobsite (approximately 4 miles away) and the precast yard.

Maximizing Efficiency in the Casting Yard

The casting yard for the 2316 box-girder segments included 12 casting cells for the segments—eight for typical segments, two for pier segments, and two for expansion-joint segments. There were also 20 reinforcing bar jigs. In addition to the box-girder segments, 160 pier-cap and column elements were cast.

Casting cells and reinforcing bar jigs were organized to allow a single crawler crane to service four casting cells. The casting cells were fitted with movable shelters to protect both the segments and workers from the weather. To ensure reinforcement was ready when the forms were ready, each cell typically had two reinforcing bar jigs.

The segments included transverse post-tensioning (PT) tendons in the deck with four 0.6-in.-diameter, 270-ksi strands that were installed, tensioned, and

Casting cells for precast concrete box-girder segments with protective covers. Photo: Johnson Bros.






Figure 1. Typical segment erection sequence of a span. Note: PS indicates pier segment and S indicates span segment. Figure: Structural Technologies.

grouted in the casting yard. The 9386 four-strand PT transverse tendons were prefabricated and individually placed in the reinforcing bar cage. To minimize the number of transverse tendon pockets that would need patching, the dead-end anchorages of the four-strand transverse tendons were cast into the deck.

Once a segment was moved off the match-cast station, it was placed on a finishing stand where any blemishes were patched, and transverse tendons were tensioned. Segments were then moved and double-stacked in the storage area where transverse tendons were grouted. With eight different erection fronts, management of segment storage was critical to ensure that proper segments were delivered to the correct span and in the correct sequence.

Heavy segment haulers were used to transport the segments to the different erection fronts. During segment transit, the haulers were escorted by local police.

Multiple Work Fronts

During segment erection, the jobsite was organized into eight work fronts. Each had its own dedicated superintendent, crews, and erection equipment. Using multiple work fronts fostered a competitive environment that motivated crews to adhere to quality, schedule, and safety goals.

Typical Span Erection

The shoring method for segment erection provided an additional benefit by reducing the time it took to erect segments. With a truss-supported method, the truss must be loaded with all segments before the segments can be joined together; this requires handling and moving the segments several times during the span erection cycle. In contrast, the shoring method does not require as much handling and moving of segments.

The span erection cycle began with the placement of shoring towers. Because the

bridge typically had four parallel lines of box girders, towers could be moved transversely from one girder line to the next or set in position using a crane. Once the shoring towers were positioned, the typical span erection progressed by placing the leading edge pier segments, followed by the span segments (Fig. 1). The PT tendons were then installed and tensioned to an initial force. Closure joints were placed and the tendons tensioned to full force once the closure pour concrete achieved the minimum required strength. At this point, the shores were released and moved to the next span. An advantage of

Using a three-dimensional model, engineers determined that several spans would require portal frames. Here, two portal frames support segments over an existing bridge. Photo: Structural Technologies.





The erection of a split-pier segment. Photo: Structural Technologies.



The erection of the first span was completed on March 11, 2019. The main elements of the shoring towers were color coded to be easily identified by field crews for their proper locations. Approximately 127 individual shoring towers were provided, which allowed concurrent work on up to eight fronts. Photo: Structural Technologies.



Sliding shoring tower. The custom shoring towers could be moved transversely for erection of an adjacent girder line. Photo: Johnson Bros.

this shoring method was that the segments could be placed and aligned in the same operation, reducing the number of times the segments needed to be handled during span erection.

Conclusion

In the I-59/I-20 project, the project team leveraged precast concrete segmental bridge construction to deliver a durable structure efficiently and maximize an early completion incentive. The strategy of using custom-designed shoring towers to allow nonlinear construction, using longer but fewer segments, and the use of precast concrete substructure elements all served to enhance constructability and reduce the contractor's risks. The project team demolished 180 spans of

existing structure in 41 days, precast 160 pier caps and columns as well as 2316 box-girder segments in 18 months, and erected the 172 spans of the new bridge in just over 7 months. This replacement structure opened in mid-January 2020 and will serve the people of Birmingham and the traveling public for years to come.

Robert W. Sward is a vice president with Structural Technologies LLC in Fort Worth, Tex.

EDITOR'S NOTE

Visit aspirebridge.org for additional information about and photos of this and other projects.

Segmental Brings Inspiration to Life.

Systems are available to **deliver form and function to maximize efficiency in a timely and economic fashion.**



Training Opportunities:

Construction Practices Handbook, New 3rd Edition

This "How-To Handbook" was developed with the purpose of providing comprehensive coverage of the state-of-the art for construction and inspection practices related to segmental concrete bridges.

The Construction Practices Handbook is a **FREE pdf download**. This link www.asbi-assoc.org/index.cfm/publications/handbook-download will take you to the registration form to complete the download.

August 17-18, 2020 –

2020 Construction Practices Seminar

Seattle Airport Marriott, Seatac, WA
Please Check the ASBI Website Events Page for Future Webinar on Select Topics.



2020 Grouting Certification Training

Please Check the ASBI Grouting Training and Events Pages for Details on Future Webinars.

October 26-28, 2020 –

Due to COVID 19, the Convention Has Been Canceled

Please Check the ASBI Website Events Page for Details of Virtual Event.



American Segmental Bridge Institute

Promoting Segmental Bridge Construction in the United States, Canada and Mexico

For information on the **benefits of segmental bridge construction** and **ASBI membership** visit: www.asbi-assoc.org

2020 ASBI GOLD SPONSOR

SEGMENTAL CONSTRUCTORS, DESIGNERS, LEADERS



Kiewit